



## General Project Requirements and General Notes

### I. PREFACE

- A. All maps, technical studies, reports, designs, construction drawings, specifications and special technical requirements associated with the project and improvements presented herein has been accomplished under the supervision of responsible Professional(s) having the appropriate registration to serve in this capacity based on the scope of this specific project, and in accordance with the statutory provisions of the Nevada Revised Statutes (NRS) and the Nevada Administrative Code (NAC) including:

NRS 278, 338, NRS 623, NRS 625; NAC 338, NAC 623 and NAC 625

Certification signifying compliance with statutory and related administrative code requirements is hereby provided by the responsible Professional(s) in the form of a stamp or seal placed on the project documents.

- B. The project and all improvements related thereto as illustrated on the project drawings must conform to North Las Vegas Municipal Code including the Titles and Chapters noted below:

Title 2, Chapter 2.36	Administrative Fees
Title 8, Chapter 8.16	Fire Code
Title 10, Chapter 10.16	Traffic Control Devices
Title 10, Chapter 10.52	Temporary Traffic Control Regulations
Title 12, Chapter 12.08	Public Works Project Permit and Performance Regulations
Title 13	Public Services
Title 15	Uniform Regulations for the Control of Drainage
Title 16	Subdivisions

It is expected that these Titles and Chapters, as a minimum, will be applied on a project specific basis and not construed to be all inclusive or exclusive. The project is also expected to conform with revisions in the North Las Vegas Municipal Code as it may be revised from time to time.

- C. Project review by representatives of the City of North Las Vegas is intended to complement and assist the responsible Professional(s) in advancing a project that is in compliance with City of North Las Vegas requirements, and is consistent with public benefit, health, safety, and welfare. Review is not an assurance of project feasibility, professional and technical accuracy, or conformance with special conditions imposed by public agencies, including the North Las Vegas Planning Commission.
- D. Approval of these improvement plans and specifications is made based on the representations made by the Professional(s) that they have discharged their responsibilities and prepared complete documents which comply with City of North Las Vegas requirements for construction of the improvements depicted herein.
- E. If construction has not commenced within, or in the event of an interruption in construction for a period of, one (1) year after the most recent approval date noted hereon, these improvement plans must be resubmitted for evaluation by the City of North Las Vegas for possible design update.

### II. STANDARD SPECIFICATIONS AND STANDARD DRAWINGS FOR GENERAL CONSTRUCTION

- A. All improvements shown on these construction drawings shall be implemented in accordance with the "Uniform Standard Specifications for Public Works Construction Off-site Improvements, Clark County Area, Nevada," latest edition. Approved revisions to these Standards are posted on the Regional Transportation Commission of Southern Nevada website.
- B. Exceptions to these Standards are noted below:
1. All provisions directly related to those procedures used to solicit competitive bids and to award and execute contracts for public agency projects.
  2. The City of North Las Vegas Trench Backfill Policy dated August 15, 1996, shall be implemented for this project. Copies of the Trench Backfill Policy can be obtained from the Department of Public Works, Construction Services Division, 50 East Brooks Avenue, North Las Vegas, Nevada 89030, 633-1320.
  3. The City of North Las Vegas Policy Regarding Grading and Construction On Or In Close Proximity To Geologic Faults and Ground Fissures. Copies of the policy can be obtained from the Department of Public Works, Construction Services Division, 50 East Brooks Avenue, North Las Vegas, Nevada 89030, 633-1320.

4. Where allowed, curb and gutter having a design grade of 0.5 percent or less shall be constructed by forming. Form grades and elevations shall be verified prior to placement of concrete and water flow tested as soon after placement as curing allows.
  5. "No parking" zones at curb returns, fire hydrant zones and school zones shall be painted red to the limits noted on the plans, or if not shown on the plans, to the limits established by the City of North Las Vegas Traffic Engineer.
- C. Modifications and clarifications to these standards are noted below:
1. The contractor shall make a project site visit with plans-in-hand prior to construction to confirm project constructability, and shall immediately notify the Professional of any constructability problems.
  2. Information noted on the plans concerning the existence and location of existing wet underground utilities and other underground structures were obtained by a search of available records. The City of North Las Vegas, Professional, and Owner make no assurances concerning the accuracy of such information. The Contractor shall exercise caution and use best available construction techniques to determine the actual location of and protection for all underground utilities whether or not they are shown on the plans. At a minimum, the contractor shall:  
Call Before You Dig 1-800-227-2600  
Call Before You Overhead 1-702-227-2929
  3. The contractor is responsible for securing all project permits and complying with all terms and conditions imposed by the permitting agencies. Agencies other than the North Las Vegas Public Works Department that may have jurisdiction or regulatory authority concerning the project include:  
City of North Las Vegas Building Department  
Clark County Health District - Division of Air Quality Management  
Nevada Department of Transportation  
Nevada Department of Environmental Protection  
US Army Corps of Engineers  
Nevada Division of Water Resources
  4. The contractor shall provide at least seventy-two (72) hours notice to each of the following agencies confirming the scheduled start of construction:  
City of North Las Vegas Utilities Division (702)633-1290  
Cox Communication (702)385-3644  
NV Energy (800)227-2600  
Embarq (800)227-2600  
Southwest Gas Corporation (800)227-2600
  5. The contractor shall exercise caution and use construction techniques to protect and preserve existing permanent survey monuments. All survey monuments disturbed shall be replaced and/or rehabilitated in accordance with Standards by a Professional Land Surveyor retained by the contractor.
  6. The contractor shall exercise caution and use construction techniques to protect and preserve existing public and private features located in close proximity to or abutting improvements shown on these plans. Restoration of damaged features shall be accomplished by the contractor at the contractor's expense to the satisfaction of the City of North Las Vegas' representative.
  7. The location of all sawcut lines for the project may be determined by the City of North Las Vegas if the location is not clearly shown on the plans or if existing conditions require adjustment to the location shown on the plans.
  8. The contractor shall cooperate and coordinate with the City of North Las Vegas' representative in providing ingress and egress to abutting properties, and shall protect such properties from project related storm water and nuisance runoff by providing temporary positive drainage control.
  9. Plantmix bituminous shall be finished to a height of between 3/8 inches and 5/8 inches above the lip of curb gutters and valley gutters.
  10. Fog seal shall be applied to plantmix bituminous surfaces after all corrections and adjustments have been made.
  11. Type V cement shall be used for all off-site improvements and the mix shall be designed for soluble sulfates in the subgrade of 1.5 percent or greater based on subgrade material sampling and testing. All mix designs shall be project specific and approved by the City of North Las Vegas representative prior to placements.

12. All manholes, valve boxes, junction structures, vaults and cleanouts that are located within the roadway limits shall be constructed to, and plated at subgrade level until such time as the aggregate base and plantmix bituminous surface has been completed. Thereafter, these items shall be adjusted to finish grade.
13. Utility boxes and vaults located in the sidewalk area are to be constructed to the finish design grade. The elevation shall be consistent with that required for the standard concrete City of North Las Vegas sidewalk even if the concrete sidewalk construction is deferred to a future date.
14. The contractor shall provide reasonable accommodations for City of North Las Vegas personnel to obtain GPS/GIS data on all underground utilities and infrastructure.
15. All off-site improvement subgrade must be certified by the Geotechnical Engineer of Record.

### **III. STANDARD SPECIFICATION AND STANDARD DRAWINGS FOR WATER LINE CONSTRUCTION**

- A. All water improvements shown on these construction drawings shall conform to the standards described below, and in order of precedence shown.
  1. "City of North Las Vegas Municipal Water Service District Service Rules and Regulations," latest edition.
  2. "Uniform Design and Construction Standards for Water Distribution Systems, Clark County Nevada," latest edition.
  3. "Uniform Standard Specification for Public Works Construction Off-site Improvements, Clark County Area, Nevada," latest edition.
- B. Exceptions to these Standards are noted below:
  1. No water main may be shut down to make connections without prior approval of the City of North Las Vegas representative.
  2. Materials used for water distribution facilities shall be included on the "City of North Las Vegas Approved Materials List," latest revision, or specifically identified and approved on these plans.
  3. All water meters two (2) inches and smaller shall be installed by the City of North Las Vegas. Note that all locations must be clearly identified and marked at the site. The service lines, laterals, meter boxes and sidewalks or collars must all be installed and set at grade or the meter will not be set.
  4. The City of North Las Vegas' trench Backfill Policy, dated August 15, 1996, shall be adhered to for this project.
- C. Modification and clarification to these Standards are as noted below:
  1. Water Metering Requirements for New Development:
    - a. Separate domestic and fire services (where applicable) are required for each dwelling unit, public, quasi-public, commercial, and/or industrial occupancy located on a single parcel or lot.
    - b. In the event that a building within an industrial or commercial subdivision is divided, separate domestic services are required for each unit.
    - c. Each parcel or lot of a commercial or residential subdivision will have a minimum of one (1) metered domestic service. When a fire service is required, each parcel or lot will have a minimum of one (1) fire service. The City, at its option, may allow a communal fire service provided the property owners first establish a property management association which accepts responsibility for the payment of water bills and the maintenance and operation of the fire lines and the backflow prevention assembly.
  2. Fire and domestic water services as approved on this plan, are intended specifically for the lot and use shown, and are not intended to serve additional parcels or structures which may be created in the future. In the event that the parcels and/or lots shown on this plan are further divided to create additional parcels or lots, the owner is required to provide separate fire and domestic water services to each.
  3. Connection to public fire hydrants shall not be made for domestic and/or private fire service.
  4. All service laterals two (2) inches and smaller shall be copper tubing with approved service saddles. Corporation stops and angle meter stops shall be the same size as the service lateral. Angle meter stops and meter shall be centered in meter the box.
  5. UDACS Plates No. 1A and 1C- Revise note to read "couplings are not allowed between the corporation stop and the angle meter".

6. All meters to be installed in the City of North Las Vegas water system, including DCDAs must be compatible with the SENSUS AMR protocol (a.k.a. Invensys) and must be installed with the encoded register. Meters that are fully compatible are: Senso/Invensys ECR/WP models (5/8" and larger) Neptune Autoread models (3" and larger).
  7. Any parcel receiving water from the public distribution system from multiple connections is required to utilize the same meter manufacturer. For master metered multi-family residential, the meters shall be of the same manufacturer, model, and size.
  8. All meter boxes shall be equipped with traffic bearing covers and installed to finish design grade and elevation. If such is not shown on the plans, the elevation will be established by the City of North Las Vegas representative.
  9. Any block wall or other fence shall be designed and constructed around the outside of the easement(s), to allow the City direct access to vault(s) and inlet piping from the adjacent right-of-way.
  10. No utility boxes shall be located in driveway approaches, unless approved by the Utilities Division.
  11. A single pipe material shall be used throughout the project unless otherwise approved by the City of North Las Vegas representative.
  12. The on-site water lines and appurtenances are private facilities not to be operated or maintained by the City of North Las Vegas, unless otherwise specified on Civil Improvements Plans.
  13. All valves will be located outside of driveways, valley gutters, and curb gutters.
  14. A minimum of two (2) valves shall be located at every mainline tee, or three (3) valves at every mainline cross.
  15. All new fire hydrants shall have a 5-1/4 inch valve opening.
  16. Two sources of water supply are required for any development with any combination of more than three (3) fire hydrants (public or private) or fire services.
  17. Minimum separations between fire systems and domestic water mains shall be six (6)-feet horizontally from exterior pipe walls and eighteen (18)-inches vertically. Minimum separation from sewer lines shall be ten (10)-feet horizontally.
  18. Pipe detector ribbon and locator balls shall be required above all water mains, service laterals that are six (6) inches and larger, and any service lateral not installed perpendicular to the main line.
  19. All water mains shall be filled, pressure tested to 200 PSI, disinfected, flushed, refilled and an acceptable water sample obtained, prior to connection by the City. Contact the City of North Las Vegas Utility Division twenty-four (24) hours in advance to schedule sampling.
  20. All backflow prevention assemblies shall be tested and certified by the City of North Las Vegas prior to placing the water system in service. No water shall be taken from a service requiring backflow prevention until the reduced pressure principle assembly has been successfully tested by the CNLV. Contact the City of North Las Vegas twenty-four (24) hours in advance to schedule testing.
  21. Limits of asphalt patches to be determined in the field by a City of North Las Vegas inspector. Patches will be a minimum of twelve (12)-feet machine replaced.
  22. Schedule Utility Inspections online at <http://cnlv-webinspection.cityofnorthlasvegas.com/>. Utility inspections must be scheduled online by 2:00 p.m. for inspections to occur the following normal working day (Monday through Friday). For after hours utility inspections, including weekends, contact Utility Customer Service at (702) 633-1277 to set up an account.
  23. Record drawings shall be prepared, signed and submitted to the City of North Las Vegas representative prior to final acceptance of any water distribution facilities to be owned, operated or maintained by the City of North Las Vegas.
- D. Shutdown requirements and information:
1. Contact the utilities Department seven (7) working days prior to any anticipated shutdown for coordination purposes. The contractor shall not open/close any valves within the City's water distribution system. The utilities department contact number is 633-1285.
  2. For commercial properties, provide written notification and verbal coordination between the Utilities Department and the commercial property owner(s) a minimum of seven (7) working days prior to anticipated shutdown. The commercial owner(s) shall have the ability to provide input in scheduling shutdowns.
  3. For residential properties, provide written notification to residential properties a minimum of 48 hours prior to anticipated shutdown.

4. Working days are deemed to be Monday through Thursday for shutdown purposes.
5. Shutdowns are anticipated to be night work. Final decisions shall be at the discretion of the Utilities Department.

#### **IV STANDARD SPECIFICATIONS AND STANDARD DRAWINGS FOR SEWER LINE CONSTRUCTION**

- A. All sewer lines (wastewater collection systems) shown on these construction drawings shall conform to the standards described below, and in accordance with the precedent shown:
  1. "Design and Construction Standards for Wastewater Collection Systems, Southern Nevada," latest edition.
  2. "Uniform Standard Specifications for Public Works construction Off-Site Improvements, Clark County Area, Nevada," latest edition.
- B. Exceptions to these Standards are noted below:
  1. Materials used for wastewater collection systems shall be included in the City of North Las Vegas approved Materials List, latest edition, or specifically identified and approved on these plans.
  2. The City of North Las Vegas Trench Backfill Policy, dated August 15, 1996 shall be adhered to for this project.
  3. The contractor shall inscribe "S", 3-inches in height, into the curb at the point where the sewer lateral enters each subdivision lot or private land parcel.
- C. Modifications and clarification to these Standards are noted below:
  1. All sanitary sewer manhole bases for new pipe must be precast per Design and Construction Standards for Wastewater Collection Systems plates SD-1A & 1B.
  2. Limits of asphalt patches to be determined in the field by a City of North Las Vegas inspector. Patches will be a minimum of twelve (12)-feet, machine replaced.
  3. The on-site sewer lines and appurtenances are private facilities not to be operated or maintained by the City of North Las Vegas, unless otherwise specified on Civil Improvement Plans.
  4. Sewer services as approved on this plan, are intended specifically for the lot and use shown, and are not intended to serve additional parcels or structures which may be created in the future. In the event that the parcels and/or lots shown on this plan are further divided to create additional parcels or lots, the owner is required to provide separate sewer services to each.
  5. Schedule Utility Inspections online at <http://cnlv-webinspection.cityofnorthlasvegas.com/>. Utility inspections must be scheduled online by 2:00 p.m. for inspections to occur the following normal working day (Monday through Friday). For after hours utility inspections, including weekends, contact Utility Customer Service at (702) 633-1277 to set up an account.
  6. Record drawings shall be prepared, signed and submitted to the City of North Las Vegas prior to acceptance of any wastewater collection systems to be owned, operated, or maintained by the City of North Las Vegas.
  7. Pipe detector ribbon and locator balls shall also be required above all sewer mains.

#### **V. OTHER GENERAL NOTES**

##### **A. General Grading and Drainage Notes**

1. Pursuant to City of North Las Vegas Ordinance Number 1172, the contractor is required to secure a grading permit prior to commencing work.
2. The contractor shall secure a permit for any off-site construction.
3. The contractor's operations shall not trespass beyond the project property lines unless a permit or written authorization has been obtained from the property owner(s) involved. Copies of such written authorization shall be furnished to the City of North Las Vegas' representative prior to start of construction.
4. The City of North Las Vegas Construction Services shall be notified one (1) working day before any on-site construction work begins.
5. An approved grading and drainage plan shall be on the job site at all times. Deviations from the approved plan will require submittal of a formal revised plan for review and approval.
6. All construction survey control shall be done by a licensed Professional Land Surveyor in accordance with applicable statutes and codes. The contractor shall provide competent resources to assure building pad and building floor elevations conform to those shown on the construction drawings. Furthermore, the contractor shall provide the City of North Las Vegas

Building Department with:

- a. Certification of "Building Floor Elevations" in critical drainage areas.
  - b. Certificates of "Building Pad Elevations" in noncritical areas.
7. The contractor shall certify to the City of North Las Vegas Construction Services Division that all fills, foundations and subgrades meet the minimum compaction requirements. Certification shall be made prior to pouring concrete.

**B. General Traffic Notes**

1. All barricading, construction signing, traffic delineation and markings shall be in accordance with the latest edition of the manual on uniform traffic control devices and/or work zone traffic control handbook. It shall be the contractor's responsibility to see that all traffic control devices are properly installed and maintained throughout the duration of the project. Contact the City of North Las Vegas' Manager of Roadway Operation for specific traffic control requirements.
2. If the project improvements necessitate temporary removal and/or relocation of traffic control signs, markings or any other traffic control devices, they shall be maintained throughout the entire duration of the project and shall be restored to the satisfaction of City of North Las Vegas' Construction Services Manager.
3. Permanent pavement marking shall be required for all rights-of-way 80 feet wide or greater which include half street improvements unless otherwise noted. New pavement markings designs shall incorporate into any existing bordering markings. Painted markings shall not be used for temporary conditions. All temporary markings shall be a removable grade tape. All other markings shall be per Clark County Uniform Standard Drawing 244 thru 248 and meet the satisfaction of the Manager of Roadway Operation.
4. All permanent traffic control devices required by Manager of Roadway Operation shall be properly installed in accordance with the latest edition of the MUTCD and/or the RTC standards prior to allowing any public traffic onto the streets, regardless of the status of their completion.
5. Fiber optic conduit schedule 40 PVC is required on all rights-of-way 80 feet and greater, size shall be 4 inches, unless otherwise specified. Pull boxes and covers shall be made of reinforced polymer concrete materials and pull box covers shall be stamped with CNLV FIBER. Pull boxes shall be of Type P 30 with straight bottom entry and exits. Spacing of pull boxes shall be 450 feet, maximum 500 feet apart, if construction limits are less than 450 feet, and one pull box shall be installed. All fiber conduits at limit of construction shall be stubbed and capped 5 feet past property line and/or connected to existing fiber conduit. All conduits shall be cleaned, blown out, mandrel(ed) and shall have a 200 lb. Pull line and a number 8 AWG THW trace wire. Pull line and wire shall be secured at both ends and capped.
6. All intersections with 80 feet/80 feet rights-of-way and greater shall be in accordance with Clark County Uniform Standard Drawing 404.1306. Location of future signal pole foundation shall be Type I and located center of radius as in accordance with Clark County Uniform Standard Drawing 404.1300 unless otherwise noted.
7. All development plans shall have a master street lighting and traffic control (signing and striping) plan sheet contained in the set which includes all units and/or phases of the project.
8. All temporary regulatory signage shall be ground mounted in accordance with Clark County Uniform Standard Drawing 249 and meet the most recent MUTCD requirements.
9. "No Parking" zones at curb returns, fire hydrant zones and school zones shall be painted red to the limits noted on the plans.

**C. General Streetlight Notes**

1. Streetlights shall be high pressure sodium 240 volt with integral type regulator ballast; controlled by a 60 amp, 240 volt circuit, two # 4 copper wire type THW; red and black colors plus one green # 8 copper wire type THW shall be grounded on each standard.
2. The locations of conduit ends of all conduit in structures or terminating at curbs shall be marked by a (X) at least 3 inches high cut into the face of curbs, gutter, or wall directly above the conduit. All conduits at limits of construction shall be stubbed and capped 5 feet past property line and / or connected to existing street lighting conduit.
3. All conduits shall be 2 inch PVC schedule 40 and shall have a minimum of 24 inches of cover in all areas.
4. All conduits for future use shall be blown out with compressed air, cleaned and provided with a 200 pound pull line; all ends of conduits shall be capped. All pull boxes and covers shall be

- made of reinforced polymer concrete materials and pull box covers shall be stamped with Street Light. All pull boxes shall be # 3½, unless otherwise noted.
5. Lamp characteristics shall conform in general to the provisions of the Clark County Uniform Standards Specifications 623 L.02.03. Wattage shall be as shown on the plans.
  6. All service panels shall be per Clark County Uniform Standard Specification drawing No. 330. The photo cell shall be a type II, Tork 2007 or equal and be mounted to the on top of the nearest permanent street light pole. A switch shall be included for manual operation (USS 623 L.02.06).
  7. All construction shall conform to Uniform Standard Drawings for Public Works Construction, City of North Las Vegas, and Uniform Standard Specifications for Public Works Construction, Clark County, Nevada, unless otherwise noted.
  8. Construction Services (390-4407) shall be notified 24 hours in advance to schedule an inspection of the wiring makeup /service point. A completed set of mylar as-builds must be submitted to Construction Services upon completion of work.
  9. Street lights shall be placed in accordance with Uniform Standard Drawing number 320 thru 320A, unless otherwise noted. Standards and mast arms shall be galvanized in accordance with ASTM A-120.
  10. Streetlight service point locations shall be provided on the off-site improvements plans and as-built plans.
  11. Internal residential streets and external arterial, collector streets shall have separate service points (RCOC / Pedestals), all services shall be limited to 80 percent capacity.
  12. An empty 2 inch schedule 40 PVC shall be place between internal and external street lighting circuit.
  13. No street lighting circuits shall cross any arterial or collector streets (excluding feeders and home runs).

**D. General Fire Department Notes**

1. All work shall be done in strict accordance with North Las Vegas' standard specifications and drawings.
2. The contractor is responsible for compliance with the 2000 Uniform Fire Code, Article 87, during construction.
3. A Knox key box is required on all buildings and shall be located 5 feet up from the ground and at theriser room or at a location agreed upon by the Fire Department. For more information and an application, call 633-1107.
4. A minimum of one fire department apparatus access road is required to all buildings. A second means of fire department apparatus access may be required by the North Las Vegas Fire Department when it is determined that a single means of access is insufficient. A minimum of two fire apparatus access roads are required for groups of 25 or more residential units.
5. Red-painted curbs and appropriate signage are required to maintain the minimum required width of the access lane. For lanes less than 32 feet wide, both sides of the lane shall be marked. For lanes less than 40 feet wide but at least 32 feet wide, one side of the lane must be marked, and only parallel parking is allowed on the other side of the lane. Signage shall be posted at the two ends of the fire lane, and additionally as required to provide maximum separation of 100 feet between signs. Signage shall state "No Parking Fire Lane"
6. Gates restricting traffic across access lanes shall be operable by the fire department. Gates shall be electrically powered, provided with an AVI loop, and have a back-up battery system in case of normal power loss. The AVI loop shall be located 10 feet perpendicularly from the face of the access gate along the route of arrival, 10 feet from the public right-of-way, and the loop shall be marked by way of a green reflective marker on the access lane. A fire department permit must be obtained prior to installing the gate(s).
7. Dead-ends longer than 150 feet shall be provided with a clear turnaround with a diameter of  
104 feet.
8. Fire hydrants must be spaced at a maximum separation of 500 feet in residential areas, 300 feet in commercial/industrial areas, and 1,000 where not required for structures to provide for transportation hazards. Hydrant spacing may be increased by 100 feet if all structures within the development are provided with sprinkler protection. There is no allowable increase for

- hydrants installed for transportation hazards.
9. On any residential or commercial construction project, accessible fire hydrants shall be installed before actual construction commences. Fire hydrants shall be provided within 300 feet of combustible material storage and framing construction. A hydrant flow test is required, which shall include static pressure and water flow volume showing the ability to meet the required fire flow, and must be presented to the North Las Vegas Fire Department and Public Works.
  10. No fire hydrants shall be located within six (6) feet of a driveway, power pole, light standard, or any other obstruction or within fifteen (15) feet of a curb return or driveway in an industrial or commercial area.
  11. The maximum allowable reduction in required fire flow for sprinklered facilities is 50%. High-rise buildings, buildings more than three stories in height, and buildings stocking high-piled combustibles and/or combustible liquids may have their required fire flow reduced by a maximum of 25%. The minimum required fire flow for any structure is 1,500 gallons per minute.
  12. When automatic fire protection is required, the fire department connection (FDC) shall be located at the DCDA and within 100 feet of a city fire hydrant, per U.D.S. plate 20B, drawing No. FS2 (11-17-97). The FDC shall be labeled with the address of the building(s) served by the associated underground fire service main.

**D. General Stormwater Notes**

1. The Owner, Site Developer, Contractor, and/or their authorized agents shall each day remove all sediment, mud, construction debris, or other potential pollutants that may have been discharged to, or accumulated in, the public rights of way as a result of construction activities associated with this site development or construction project. Such materials shall be prevented from entering the storm sewer system.
2. Additional construction site discharge best management practices may be required of the owner or his/her agents due to unforeseen erosion problems or if the submitted plan does not meet the performance standards specified in the City of North Las Vegas and the *Las Vegas Valley Construction Site BMP Guidance Manual*.
3. Temporary or permanent stabilization practices will be installed on disturbed areas as soon as practicable and no later than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Some exceptions may apply; refer to the Nevada Stormwater General Permit for Construction Activity NVR100000, Section III.A.5.
4. At a minimum, the Contractor or his agent shall inspect all disturbed areas, areas used for storage of materials and equipment that are exposed to precipitation, vehicle entrance and exit locations, and all BMPs weekly, and within 24 hours after any rain event of 0.5 inches or more. The Contractor or his agent shall update or modify the Stormwater Pollution Prevention Plan as necessary. Some exceptions to weekly inspections may apply, such as suppression of land disturbance activities. Refer to the Nevada Stormwater General Permit for Construction Activity NVR100000, Section III.A.12.
5. Accumulated sediment in BMPs shall be removed within seven days after a stormwater runoff event or prior to the next anticipated storm event, whichever is earlier. Sediment must be removed when BMP design capacity has been reduced by 50 percent or more.